INFRASTRUCTURE TECHNOLOGIES

www.csiro.au

14 Julius Avenue, North Ryde NSW 2113
PO Box 310, North Ryde NSW 1670, Australia
T (02) 9490 5444 • ABN 41 687 119 230



Certificate of Test

No. 2668

"Copyright CSIRO 2015 ©"

Copying or alteration of this report without written authorisation from CSIRO is forbidden.

This is to certify that the element of construction described below was tested by the CSIRO Infrastructure Technologies in accordance with Australian Standard 1530, Methods for fire tests on building materials, components and structures, Part 4-2005 on behalf of:

Brickworks Building Products Pty Ltd 738-780 Wallgrove Road HORSLEY PARK NSW

A full description of the test specimen and the complete test results are detailed in the Division's Sponsored Investigation report numbered FSV 1705.

Product Name: Non-loadbearing Pronto Panel wall system.

Description: The specimen comprised a non-loadbearing Pronto Panel wall system. The overall dimensions of the wall assembly were

3000-mm high x 3000-mm wide x 60-mm thick, the wall was mounted into a 3015-mm high x 3000-mm wide double

brick wall opening.

The panel wall was built using five Pronto Panels, each nominally 3000-mm high x 610-mm wide x 60-mm thick. The Pronto Panel consisted of a cement matrix with polystyrene aggregate. The panels were faced on both sides with 5-mm thick fibre cement boards adhered to the core with a polymer adhesive. The panels were unreinforced and had a stated density of 865 kg/m^3 .

The vertically laid panels were restrained along the top, bottom and one vertical edge using 75-mm x 50-mm x 1.2-mm BMT slotted steel angles. The angles were fixed to the top and bottom of the brick opening using 50-mm long x 6.5-mm diameter metal sheathed masonry anchors at nominal 600-mm centres. The panels were fixed to the steel angles from the exposed side only, using two 50-mm long 14-10 hex head type 17 screws per panel at 300-mm nominal centres. The panels incorporated tongue and groove butt joints, and were joined together with Pronto Adhesive Compound. A 10-mm wide expansion gap was left along the head of the panel wall sealed from the unexposed side with Bostik Fireban One polyurethane sealant to a nominal depth of 30-mm, controlled by a backing rod.

Details of construction is shown in drawings PR 030-PR 031, both dated 14 July 2015, by Brickworks Building Products.

The element of construction described above satisfied the following criteria for fire-resistance for the period stated.

Structural Adequacy not applicable Integrity 87 minutes Insulation 80 minutes

and therefore for the purpose of Building Regulations in Australia, achieved a fire-resistance level (FRL) of -/60/60. The FRL is applicable for exposure to fire from the same direction as tested.

This certificate is provided for general information only and does not comply with regulatory requirements for evidence of compliance.

Testing Officer: Chris Wojcik Date of Test: 27 July 2015

Issued on the $\mathbf{24}^{\text{th}}$ day of August 2015 without alterations or additions.

Brett Roddy

Manager, Fire Testing and Assessments



B. Rong

NATA Accredited Laboratory
Number: 165
Corporate Site No 3625
Accredited for compliance with ISO/IEC 17025