

IAN BENNIE AND ASSOCIATES

TEST REPORT NO. 20218S2

TERRACADE 150 MM TILE CLADDING
PROTOTYPE TEST to AS/NZS4284-1995

for
Austral Brick Company

October 2002



Registered Laboratory No. 2371



IAN BENNIE & ASSOCIATES PTY. LTD.
Building Performance Testing

ACN : 007 133 253



Registered
Laboratory
No. 2371

TEST NUMBER 20218S2

Client: Austral Brick Company

Sample

Identification: A Terracade 150 mm tile cladding sample, spanning 3 tiles (1800 mm) in width by 3 tiles (450 mm) in height. Tiles were hung on horizontal aluminium rails (Type A-01) fixed to vertical steel top hat sections. The sample is detailed in the Fitzpatrick & Partners drawings D.sk-101, B30A, B31 and B41B, attached to this report.

Test Method: Structural and Proof testing to the requirements of Australian Standard AS/NZS4284-1995, was carried out to determine the stiffness and strength of the aluminium rail over a bay width of 1800 mm and to verify that the sample could sustain the specified pressure and suction loads without collapse.

Test Location: Austral plant, Sydney

Test Date(s): 18 July 2002.

TEST RESULTS

Structural and Proof testing were carried out using an open-faced chamber. In order to apply the loads, the faces of the tiles were covered with plastic sheeting to reduce leakage and pressures were applied in sequence. No allowance was made for load sharing by a backing wall, all load being borne by the tiles.

Structural Tests

Method

Tests were carried out in accordance with Section 7.3 of Australian Standard AS/NZS4284:1995 to pressures nominated by Hyder Consulting. Measurements were taken on the aluminium rail at the fixing points (locations 2 & 4) to the top hat and at midspan (location 3) to determine its deflection. Measurements were also taken on the top hats (locations 1 & 5) to check if there was any differential movement at the fixing. All displacement measurements were referenced to the chamber frames. Before testing, each displacement transducer was calibrated with the measuring system against NATA certified gauge blocks. Measurement accuracy for subsequent displacement data may be taken as ± 0.2 mm. All pressure transducers were calibrated against NATA certified manometers and may be taken to have a measurement accuracy of 1%.

Requirements (default values specified)

Maximum deflection of rail: Span/290

Maximum successive member residual displacement : 3.0 mm

Maximum total member displacement limit: ± 20 mm

Nominated test pressures: ± 2.5 kPa

20218S2 - Page 1 of 6

Table 1

**TEST NUMBER 1 - MODE 1
DISPLACEMENTS (mm) - POSITIVE PRESSURE**

DATAFILE 713		TEST NUMBER 1					DATE : 18/07/2002		
Reading	Pressure (kPa)	MEASUREMENT LOCATION NUMBER							
		1	2	3	4	5			
Takeup	2.50								
Z1	0.00	0.0	0.0	0.0	0.0	0.0			
		Subsequent displacements are referenced to Z1							
P1	0.51	0.2	0.2	1.5	0.2	0.1			
P2	0.95	0.3	0.5	2.8	0.4	0.3			
P3	1.49	0.5	0.7	4.3	0.5	0.4			
P4	1.97	0.6	0.9	5.3	0.6	0.6			
P5	2.49	0.8	1.1	6.5	0.8	0.7			
Z2	0.00	0.0	0.0	0.2	-0.1	0.0			
P6	2.52	0.8	1.1	6.6	0.8	0.7			
P7	2.07	0.7	1.0	5.8	0.7	0.6			
P8	1.49	0.5	0.8	4.4	0.5	0.5			
P9	1.02	0.4	0.6	3.2	0.3	0.3			
P10	0.49	0.2	0.3	1.6	0.1	0.2			
Z3	-0.00	-0.0	0.0	0.2	-0.1	0.0			

Table 2

TEST NUMBER 1 - MODE 2
DISPLACEMENTS (mm) - NEGATIVE PRESSURE

DATAFILE 713		TEST NUMBER 1					DATE : 18/07/2002		
Reading	Pressure (kPa)	MEASUREMENT LOCATION NUMBER							
		1	2	3	4	5			
Takeup	-2.52								
Z4	0.00	-0.1	-0.1	-0.5	-0.2	-0.1			
Shift during takeup		-0.1	-0.1	-0.6	-0.1	-0.1			
		Subsequent displacements are referenced to Z4							
N1	-0.49	-0.1	-0.2	-1.3	-0.1	-0.1			
N2	-1.00	-0.2	-0.5	-2.7	-0.3	-0.2			
N3	-1.52	-0.3	-0.8	-3.9	-0.6	-0.3			
N4	-1.99	-0.5	-1.0	-5.0	-0.7	-0.4			
N5	-2.51	-0.5	-1.3	-6.1	-0.9	-0.5			
Z5	0.00	-0.0	-0.0	0.1	0.0	-0.0			
N6	-2.48	-0.5	-1.3	-6.1	-0.9	-0.5			
N7	-2.04	-0.5	-1.1	-5.4	-0.8	-0.4			
N8	-1.48	-0.4	-0.9	-4.3	-0.6	-0.4			
N9	-1.02	-0.3	-0.7	-3.1	-0.4	-0.3			
N10	-0.50	-0.2	-0.3	-1.6	-0.1	-0.1			
Z6	0.00	-0.0	-0.1	0.0	0.0	-0.0			

Table 3

**TEST NUMBER 1 - MODE 3
DISPLACEMENTS (mm) - POSITIVE PRESSURE**

DATAFILE 713		TEST NUMBER 1					DATE : 18/07/2002		
Reading	Pressure (kPa)	MEASUREMENT LOCATION NUMBER							
		1	2	3	4	5			
Takeup	2.49								
Z7	0.00	-0.0	0.0	0.1	-0.3	-0.1			
Shift during takeup		0.1	0.2	0.5	-0.1	-0.0			

Table 4


**SUCCESSIVE ZERO-PRESSURE DISPLACEMENTS (mm)
REFERENCED TO THE ZERO AFTER TAKEUP IN MODE 1**

DATAFILE 713		TEST NUMBER 1					DATE : 18/07/2002		
Reading (Referenced to Z1)	MEASUREMENT LOCATION NUMBER								
	1	2	3	4	5				
Z1 - Takeup - Mode 1	0.0	0.0	0.0	0.0	0.0				
Z2 - Middle - Mode 1	0.0	0.0	0.2	-0.1	0.0				
Z3 - End - Mode 1	-0.0	0.0	0.2	-0.1	0.0				
Z4 - Takeup - Mode 2	-0.1	-0.1	-0.5	-0.2	-0.1				
Z5 - Middle - Mode 2	-0.1	-0.1	-0.4	-0.2	-0.1				
Z6 - End - Mode 2	-0.1	-0.1	-0.4	-0.2	-0.1				
Z7 - Takeup - Mode 3	-0.0	0.0	0.1	-0.3	-0.1				


Table 5

STRUCTURAL PERFORMANCE


DATAFILE 713		TEST NUMBER 1			DATE : 18/07/2002		
MEMBER	PRESSURE (kPa)	DISPLACEMENTS (rounded to 0.1 mm)			BENDING DEFLECTION (rounded to 0.01 mm)	SPAN L (mm)	SDR L/DEF
		LEFT OR TOP	CENTRE	RIGHT OR BOTTOM	DC - $\frac{D1+D2}{2}$		
		D1 (mm)	DC (mm)	D2 (mm)	DEF (mm)		
2,3,4	ALUMINIUM EXTRUSION						
	0.51	0.2	1.5	0.2	1.28	1695	1328
	0.95	0.5	2.8	0.4	2.33		728
	1.49	0.7	4.3	0.5	3.69		459
	1.97	0.9	5.3	0.6	4.55		373
	2.49	1.1	6.5	0.8	5.51		308
	2.52	1.1	6.6	0.8	5.62		301
	2.07	1.0	5.8	0.7	4.94		343
	1.49	0.8	4.4	0.5	3.78		448
	1.02	0.6	3.2	0.3	2.79		608
	0.49	0.3	1.6	0.1	1.42		1195
	-0.49	-0.2	-1.3	-0.1	-1.09		-1552
	-1.00	-0.5	-2.7	-0.3	-2.28		-744
	-1.52	-0.8	-3.9	-0.6	-3.27		-519
	-1.99	-1.0	-5.0	-0.7	-4.10		-413
	-2.51	-1.3	-6.1	-0.9	-5.01		-338
	-2.48	-1.3	-6.1	-0.9	-5.05		-335
	-2.04	-1.1	-5.4	-0.8	-4.47		-379
	-1.48	-0.9	-4.3	-0.6	-3.56		-476
	-1.02	-0.7	-3.1	-0.4	-2.60		-652
	-0.50	-0.3	-1.6	-0.1	-1.35		-1255




elevation




section



horizontal section



Austral EXTRUDED WALL CLADDING SYSTEM	Name: Architect/Drawn Title: Architect Date: 12.06.20 Scale: 1:1 Drawing No: 1	Project: Location: Client: Architect: Engineer: Designer: Drafter: Checker: Approver: Date:	<table border="1"> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>											litzpatrick + partners 23 BRIDGE ROAD SUITE 404 MELBOURNE VIC 3000 AUSTRALIA TEL +61 3 9516 8817 FAX +61 3 9516 8857 www.litzpatrick.com.au	Drawing No: 156 Title: 1/30/20 Scale: 1:1 Date: 12.06.20




Drawing B.30A

0 10 20 40 100

austral hyder 1+P

testing panel: typical vertical section



Drawing B.31

0 10 20 40 100

gustaf	hyder	f+p
--------	-------	-----

testing panel: typical horizontal section

aluminium channel, screw fixed to horizontal rails at 1200mm vertical c/s
75x38mm zincalume top hat, masonry anchor fixing to structural wall + screw fixing to horizontal rails at 1200mm vertical c/s